

Date: July 12, 2024 To: All Vendors Subject: Addendum #2

REFERENCE: **B058-24 CONSTRUCTION OF AIRPORT SUBSTATION AND CONTROL BUILDING**

This Addendum forms part of the contract and clarifies, corrects or modifies original bid document.

Question 1: Will this project be a turnkey job?

Answer 1: Yes, it is a turnkey job. The awarded contractor will be responsible for the construction and installation of substation and control building.

Question 2: Who is going to be responsible for the site grading?

Answer 2: Brownsville PUB already has a contractor to do the site grading and preparation for the new installation of the substation and control building.

Question 3: Do you have a Geotechnical report ready and available?

Answer 3: Yes, attached is the Geotechnical report.

Question 4: Do you need any access road at this site?

Answer 4: No, it is not required.

Question 5: Will Brownsville PUB also be going out for bid on AFDE-138kV A-Frame Deadend Structure and 138kV Large Angle Dead-End? The Bid B058-24 states those structures will be furnished by owner (BPUB).

Answer 5: Brownsville PUB already purchased those units, and they will be provided at the time of the construction.

Question 6: Who is going to be responsible to tap the transmission lines to A-Frame deadend structures and to energize?

Answer 6: Brownsville PUB will be responsible.

Question 7: What are the calendar days to complete the project?

Answer 7: Brownsville PUB does not have a specific number of calendar days to complete the project. BPUB will consider it when reviewing/evaluating the bids.

Question 8: Is the contractor responsible to pick up, move, transport, and deliver the equipment to the job site? Will BPUB load our trucks with the owner furnished material or is it the responsibility of the contractor to load? What is the distance?

Answer 8: Yes, this project is a turnkey job, and the awarded contractor will be responsible to move the equipment to the job site. contractor will have to coordinate pickup with BPUB on Structural steel pickup and other equipment, and responsible to provide their own loading equipment (forklift, winch truck). The equipment is located at 1495 Robinhood Drive, Brownsville TX, and the travel distance is approximately 3 to 4 miles away. A second unit is located at the Airport Substation, 915 S. Central Avenue, Brownsville, TX about 500 ft away.

Question 9: What about if moving the equipment for the second time? Do we need to move it to the new foundation?

Answer 9: Yes, the awarded contractor will be responsible for moving the equipment the second time.

Question 10: Do you have the weight and dimensions of the equipment?

Answer 10: Yes, attached is a picture of the nameplate and manufacturer design as references.

Question 11: It was mentioned yesterday that the contractor is responsible for the top rock/insulating rock that gets placed inside the station. There is not a bid unit for that, where do we need to put the cost for this?

Answer 11: Yes, see attached Cost Sheet – "Additional Line Item" page 35 rev1 and complete it along with the original cost sheet provided when submitting bid response.
 DO NOT FILL PRICING WHEN ACKNOWLEDGING RECEIPT OF THIS ADDENDUM.

The signature of the company agent, for the acknowledgement of this addendum, shall be required. <u>Complete information below and return via e-mail to: hlopez@brownsville-pub.com and to dsolitaire@brownsville-pub.com.</u>

I hereby acknowledge receipt of this addendum.

Company:		
Agent Name:		
Agent Signature:		

If you have any further questions about the Bid, call 956-983-6375.

Hugo E. Lopez


BY: Hugo E. Lopez Purchasing


REVISED COST SHEET - Additional LineItem

Drawing Ref.	NAME AND DESCRIPTION OF CONSTRUCTION UNIT	Owner Furnished	NO. OF UNITS	LABOR P	RICE	Materia	al Price
AP-Q4	25kV Porcelain Insulator Painting- Contractor is responsible for supplying labor, material, and equipment to apply 570 High Voltage Insulator Coating ("Seal Guard," Midsun Group, 1-800-4-MIDSUN) to prevent excess leakage current, tracking and flashover to new insulators. Seal Guard shall not be applied to anything made of polymer. The contractor is responsible to be fully trained or have a Midsun supervisor present during application so there is a full warranty in effect following application. The Midsun Insulator Coating is contractor furnished and WHITE in color. The porcelain insulators shall be painted in a dust-free environment (i.e. paint booth or other environment protected area.) INSULATOR COATING SHALL BE ADDED TO ALL NEW STATION POST INSULATORS, INCLUDING INSULATORS MOUNTED ON NEW SWITCHES.	Ζ	1 lot				
				TOTAL, GROUP Q			
GROUP T	- TESTING						
AP-T1	Field Testing, check-out and acceptable testing of the substation facilities as described in the Division FT of the "Contract Documents". The substation testing, check-out and acceptance will be performed by:	NA	1 lot				
				TOTAL, GROUP			
TOTAL SUBSTATION BID AMOUNT			\$				
	TOP ROCK/INSULATIN ROCK (INSIDE THE STATION)	CK (INSIDE THE STATION) 1 LOT					

ONOT FULL DD

NOTE: LINE ITEM IN RED IS AN ADDITIONAL LINE ITEM






~

	4 4 5 5 6 7 7 10 10 10 10 10 6 6 7 7 5 5 5 5 5 5 6 6 7 7 4 4 4 4 4 5 5 6 6 7 7 7 8 8 9 9 9 9 9 9 10 10 7	SERIAL NU CLASS: ON KVA: 150 KVA: 150 KVA: 168 KVA: 168 HV: 1247 LOW VOLTAGE LOW VOLTAGE VI 10 10 10 10 10 10 10 10 10 10 10 10 10 1	\
\triangleleft	8K 5R 5R 5R 3R 1R 1R 1R 1L 5L 5L 11L 9L 13L 13L 13L 15L 16L	MBER MBER 000/00/00/00/00/00/00/00 000/00/00/00/0	
	13069 13069 12969 12769 12769 12769 12770 12270 12270 12271 12270 12271 12771 12771 12771 12771 12771 12771 12771 12771 11772 11772 11572 11572 11573 11223 11273 11273 11173		
<	11226 11237 11247 11256 11266 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296 11296	5MA067- (ONAF) /25000 /28000 /28000 BIL: 00 BIL: 1174 1174 1174 1174 1174 1174 1174 1174 1174 1209 1209	
VIRGINIA R(DELC	
VIA Ro/		RISE RISE) レ >
A TRAN Roanoke,		E E MATERIAL: COPPER MATERIAL: COPPER POS. CONNECTIONS POS. CONNECTIO	
I, VA,			
ORME			
AER			
CORP			
		HZ AT 15000 KVA MINERAL OIL MANUFACTURE: 3 3 4 1 3 3 4 1 3 3 4 1 3 3 4 1 3 3 4 1 1 5 0 0 1 1 2 3 3 4 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 5 0 0 0 1 1 1 1	RANCEORMER
			רטער
			0
OPERATE		CORE & COILS TANK & FITTINGS LIQUID: MAIN TANK <u>3858</u> U.S. GALS LTC TANK <u>268</u> U.S. GALS TOTAL WEIGHT UNITANKING WEIGHT (HEAVIEST PIECE) MAX. OPERATING PRESSURES OF I <u>9</u> Ibf/in ² POSITIVE, <u>7</u> Ibf TANK DESIGNED FOR <u>15</u> Ibf/in 25°C OIL LEVEL TO TOP FLANGE O LIQUID LEVEL CHGS. <u>0.82</u> IN. P REFER TO INSTRUCTION MANUAL <u>L</u> UNIT CONTAINS NO DETECTABLE LI UNIT CONTAINS NO DETECTABLE LI UNIT CONTAINS NO DETECTABLE LI THE TIME OF MANUFACTURE	
OPERATE MANUAL TAP TRANSFORMER IS		COILS FITTINGS FITTINGS EIGHT GEGEN FING PRESSURE CHGS 0.82 CHGS 0	NPPROXIM
		CORE & COILS TANK & FITTINGS LIQUID: MAIN TANK <u>3858</u> U.S. GALS. <u>338</u> LICT TANK <u>268</u> U.S. GALS. <u>292</u> TOTAL WEIGHT UNTANKING WEIGHT (HEAMEST PIECE) MAX. OPERATING PRESSURES OF LIQUID PRESER <u>9</u> Ibf/in ² POSITIVE, <u>7</u> Ibf/in ² NECATIVE. <u>1020</u> MAX. OPERATING PRESSURES OF LIQUID PRESER <u>9</u> Ibf/in ² POSITIVE, <u>7</u> Ibf/in ² NECATIVE. <u>1020</u> MAX. OPERATING PRESSURES OF LIQUID PRESER <u>9</u> Ibf/in ² NOCUUM FIL 25°C OIL LEVEL TO TOP FLANGE OF MANHOLE, _ LIQUID LEVEL CHGS. <u>0.82</u> IN. PER 10°C CHG. NREFER TO INSTRUCTION MANUAL <u>LF-4</u> BEFORE E UNIT CONTAINS NO DETECTABLE LEVEL(<1 PPM) THE TIME OF MANUFACTURE H2 MR 12005 MR 12005 MR 12005 MR	APPROXIMATE_WEIGHT
TION CHANGER ONLY WHEN DE-ENERGIZED		36400 33850 29290 102000 102000 36820 10'C CHG. IN L 4 BEFORE ENERG 2.(<1 PPM) OF F EL(<1 PPM)	HT IN LBS
WHEN		00 150 1200 11200-5 0 1200-5 0 1200-5 0 1200-5 0 1200-5 0 1200-5 0 1200-5 0 1200-5 0 1200-5 0 0 0 0 0 0 0 0 0 0 0 0 0	SE
			•

ALL DIMENSIONS IN INCHES & IN mm IF SHOWN IN PARENTHESIS THIS DOCUMENT IS INTENDED FOR COORDINATION PURPOSES ONLY. OTHER USES ARE PROMISTED EXCEPT BY WRITTEN PERMISSION OF VTC. BY WRITTEN PERMISSION OF VTC.





Airport Distribution Substation

Brownsville, Texas

May 18, 2020 Terracon Project No. 88205026

Prepared for:

Brownsville Public Utilities Board Brownsville, Texas

Prepared by:

Terracon Consultants, Inc. Pharr, Texas

Facilities

🦲 Ge



May 18, 2020



Brownsville Public Utilities Board (BPUB) 1425 Robinhood Street Brownsville, Texas 78521

- Attn: Emmanuel Benitez, P.E. P: [956] 983-6216 E: ebenitez@brownsville-pub.com
- Re: Geotechnical Engineering Report Airport Distribution Substation Billy Mitchel Blvd. and S. Central Ave. Brownsville, Texas Terracon Project No. 88205026

Dear Mr. Benitez:

We have completed the Geotechnical Engineering services for the above referenced project. This study was performed in general accordance with Terracon Proposal No. P88205026 dated January 28, 2020. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundations for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely, Terracon Consultants, Inc. (Texas Firm Registration No.: F-3272)

mt.

Stephany Chacón, E.I.T. Staff Engineer



Alfonso A. Soto, P.E., D.GE Principal

Terracon Consultants, Inc. 1506 Mid Cities Drive Pharr, TX 78577 P [956] 283 8254 F [956] 283 8279 terracon.com

REPORT TOPICS

REPORT SUMMARY	1
NTRODUCTION	. 1
SITE CONDITIONS	. 1
PROJECT DESCRIPTION	. 2
GEOTECHNICAL CHARACTERIZATION	. 2
GEOTECHNICAL OVERVIEW	. 3
EARTHWORK	. 4
FOUNDATIONS SYSTEMS	. 9
SEISMIC CONSIDERATIONS	21
FLOOR SLABS	21
GENERAL COMMENTS	23

Note: This report was originally delivered in a web-based format. **Orange Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the *GeoReport* logo will bring you back to this page. For more interactive features, please view your project online at <u>client.terracon.com</u>.

ATTACHMENTS

EXPLORATION AND TESTING PROCEDURES SITE LOCATION AND EXPLORATION PLANS EXPLORATION RESULTS SUPPORTING INFORMATION

Note: Refer to each individual Attachment for a listing of contents.



REPORT SUMMARY

Topic ¹	Overview Statement ²	
Project Description	The project will include the construction of substation and transmission line related equipment.	
 Geotechnical Characterization Groundwater was encountered at depths between 7 and 34 feet be existing grade during drilling operations. The subsurface soils at this site generally consist of Fat Clay (CH) and S Sand (SM). 		
Potential Vertical Rise (PVR)	The existing Potential Vertical Rise (PVR) of the soils within the proposed building area in present condition is about 1 to 2 inches.	
Seismic Site Classification	The subsurface conditions within the site are consistent with the characteristics of Site Class D as defined in the International Building Code (IBC) Site Classification.	
Earthwork	The subgrade should be prepared as noted in Earthwork	
FoundationsA shallow or deep foundation system would be appropriate to support the str loads of the proposed structures, provided the pads are prepared as recomm in this report.		
General This section contains important information about the limitations of this ge		
Comments engineering report.		
 If the reader is reviewing this report as a pdf, the topics above can be used to access the appropriate section of the report by simply clicking on the topic itself. This summary is for convenience only. It should be used in conjunction with the entire report for design 		

purposes.

Airport Distribution Substation Billy Mitchel Blvd. and S. Central Ave. Brownsville, Texas Terracon Project No. 88205026 May 18, 2020

INTRODUCTION

This report presents the results of our subsurface exploration and geotechnical engineering services performed for the proposed additions to the existing Airport Distribution Substation located at Billy Mitchel Blvd. and S. Central Ave. in Brownsville, Texas. The purpose of these services is to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Groundwater conditions
- Site preparation and earthwork
- Excavation considerations

- Foundation design and construction
- Floor slab design and construction
- Seismic site class per IBC

The geotechnical engineering Scope of Services for this project included the advancement of 3 test borings to depths of approximately 50 feet below existing site grades.

Maps showing the site and boring locations are presented in the **Site Location** and **Exploration Plan** sections, respectively. The results of the laboratory testing performed on soil samples obtained from the site during the field exploration are included on the boring logs in the **Exploration Results** section.

SITE CONDITIONS

The following description of site conditions is derived from our site visit in association with the field exploration and our review of publicly available geologic and topographic maps.

Item	Description		
Barrad Information	The project site is located south of the intersection of Billy Mitchel Blvd. and S. Central Ave. in Brownsville, Texas.		
Parcel Information	Latitude/Longitude: 25.906247°, -97.447431°		
	See Site Location		
Existing Improvements	Currently energized and operational substation		
Current Ground Cover	r Caliche		
Existing Topography	Relatively flat and level.		

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



ltem	Description		
Geology	Based on the Geologic Atlas of Texas, McAllen – Brownsville prepared by The University of Texas, the site is located on the Alluvium Formation of the Holocene (Recent) Period of the Quaternary Age. Floodplain deposits, lower course of Rio Grande, are divided into areas dominantly mud and areas dominantly silt and sand. All other areas are alluvium undivided, except for some areas where tidal flat areas are mapped. The soils are mostly composed of clay, silt, sand, gravel and organic matter. The silt and sand are described as calcareous and dark gray to dark brown in color. The sand is mostly quartz and the gravel along Rio Grande include sedimentary rocks from the Cretaceous and Tertiary and a wide variety of igneous and sedimentary rocks from Trans-Pecos Texas, Mexico, and New Mexico including agate. The gravel in side streams of the Rio Grande is mostly Tertiary rocks and chert derived from Uvalde Gravel which caps divide.		

PROJECT DESCRIPTION

Item	Description		
Information Provided	<i>Technical Specifications for the Scope of Work</i> provided by Brownsville Public Utilities Board via email on 01/24/2020.		
Project Description	The project will include the construction of substation and transmission line related structures and equipment.		
Construction Type	The proposed structures may be supported by a shallow (grade-supported pads and mats) and/or deep (straight-sided drilled shafts or direct embedded poles) foundation system.		

GEOTECHNICAL CHARACTERIZATION

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of site preparation and foundation options. Conditions encountered at each exploration point are indicated on the individual logs. The individual logs and the GeoModel can be found in the Exploration Results section of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



Model Layer	Layer Name	General Description
4	CLAY	Fat Clay (CH)
	CLAY	Soft to hard
2	2 SAND	Silty Sand (SM)
2		Loose to very dense

Groundwater Conditions

The boreholes were observed during and after completion of drilling for the presence and level of groundwater. The water levels observed are noted on the attached boring logs, and are summarized below.

	Depth to groundwater (feet)			
Location	During drilling	15 minutes after initial groundwater reading	After boring completion	
B-1	34	34	7	
B-2	16	12	7½	
B-3	13	8	8	

The Silty Sand (SM) soils are considered volumetrically stable and due to their granular nature may transmit water easily during rainfall seasons. Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than the levels indicated on the boring logs. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project. The boreholes were backfilled with cement-bentonite grout after completion of the groundwater level observations.

GEOTECHNICAL OVERVIEW

Our findings indicate the proposed building structure can be supported on a shallow or deep foundation system. The desired foundation system may be used at this site provided the site and foundation are designed and constructed as recommended in this report.

The suitability and performance of a soil supported foundation for a structure depends on many factors including the magnitude of soil movement expected, the type of structure, the intended use of the structure, the construction methods available to stabilize the soils, and our understanding of the owner's expectations of the completed structure's performance.



Expansive soils and soft compressible soils are present on this site. This report provides recommendations to help mitigate the effects of soil settlement, shrinkage and expansion. However, even if these procedures are followed, some movement in the structure should be anticipated. Eliminating the risk of movement may not be feasible, but it may be possible to further reduce the risk of movement if significantly more expensive measures are used during construction. We would be pleased to discuss other construction alternatives with you upon request.

Geotechnical engineering recommendations for foundation systems and other earth connected phases of the project are outlined below. The recommendations contained in this report are based upon the results of data presented herein, engineering analyses, and our current understanding of the proposed project.

The General Comments section provides an understanding of the report limitations.

Swell Test Results

To further evaluate the expansive characteristics of the clayey soil, one-dimensional vertical swell tests were conducted on selected specimens. The results of these tests are shown in the following table.

	Swell Test Results				
Boring	Depth (feet)	Surcharge (psf)	Initial Moisture (%)	Final Moisture (%)	Percent Swell (%)
B-1	5.0	100	25.5	27.3	0.8
B-1	5.0	700 ¹	24.5	26.0	0.1
1. Swell	1. Swell test specimens were applied a surcharge pressure during testing that approximated the existing soil				

 Swell test specimens were applied a surcharge pressure during testing that approximated the existing soil overburden.

The test results indicate that the onsite soils have a moderate swell potential in their existing condition. However, these soils, if they were allowed to dry out, could have greater potential for volumetric changes.

EARTHWORK

Earthwork will include clearing and grubbing, excavations and fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria as necessary to render the site in the state considered in our geotechnical engineering evaluation for foundations and pavements.

May 18, 2020 - Terracon Project No. 88205026



Site Preparation

Construction areas should be stripped of all caliche, topsoil and other unsuitable material. Additional excavation as recommended in this report or as needed should be performed within the proposed building area. Once final subgrade elevation has been achieved, the exposed subgrade should be carefully proofrolled with a 15-ton pneumatic roller or a fully loaded dump truck to detect weak zones in the subgrade. Special care should be exercised when proofrolling the fill soils to detect soft/weak areas. Weak areas detected during proofrolling, as well as zones of fill containing organic matter and/or debris should be removed and replaced with select fill in the proposed building area. Proper site drainage should be maintained during construction, so that ponding of surface runoff does not occur and cause construction delays and/or inhibit site access.

Subsequent to proofrolling, and just prior to placement of fill, the exposed subgrade within the construction area should be evaluated for moisture and density. If the moisture, density, and/or the requirements do not meet the criteria described in the table below, the subgrade should be scarified to a minimum depth of 8 inches, moisture adjusted and compacted to at least 95 percent of the Standard Effort (ASTM D 698) maximum dry density. Select fill should meet the following criteria.

Fill Material Types

Engineered fill should consist of approved materials, free of organic material, debris and particles larger than about 2 inches. The maximum particle size criteria may be relaxed by the geotechnical engineer of record depending on construction techniques, material gradation, allowable lift thickness and observations during fill placement. Soils for use as engineered fill material should conform to the following specifications:

Fill Type ¹	USCS Classification	Acceptable Location for Placement		
Aggregate Base Course ²	SC, GC, Caliche, Crushed Limestone, Crushed Concrete	Top 6 inches of pad areas.		
Select Fill	CL and/or SC (7≤PI≤20)	Must be used to construct the pads under the structures and all grade adjustments.		
On-Site Soils	On-Site SoilsCL/CHOn-site CL soils may be suitable for use as fill with the structure areas as long as they are free fro organics, cohesive and have a PI between 7 and 20			
 Prior to any filling operations, samples of the proposed borrow and on-site materials should be obtained for laboratory moisture-density testing. The tests will provide a basis for evaluation of fill compaction by in- place density testing. A qualified soil technician should perform sufficient in-place density tests during the 				



filling operations to evaluate that proper levels of compaction, including dry unit weight and moisture content, are being attained.

2. Crushed limestone and crushed concrete material should meet the requirements of 2014 TxDOT Item 247, Type A, or D, Grades 1-2 and 3. The select fill materials should be free of organic material and debris, and should not contain stones larger than 2 inches in the maximum dimension. The clayey gravel and caliche materials should meet the gradation requirements of Item 247, Type B, Grades 1-2 and 3 as specified in the 2014 TxDOT Standard Specifications Manual and a Plasticity Index between 7 and 20.

Fill Compaction Requirements

Structural and general fill should meet the following compaction requirements.

Item	Description
Fill Lift Thickness	The fill should be placed in thins; loose lifts of about 8 inches, with compacted thickness not exceeding 6 inches.
Compaction Requirements (on-site soils)	The on-site soils should be compacted to at least 95 percent of the Standard Effort (ASTM D698) maximum dry density within 4 percentage points above the optimum moisture content.
Compaction Requirements (select fill)	The select fill should be compacted to at least 95 percent of the Standard Effort (ASTM D698) maximum dry density within 2 percentage points of the optimum moisture content.

Wet Weather/Soft Subgrade Conditions

Construction operations may encounter difficulties due to the wet or soft surface soils becoming a general hindrance to equipment due to rutting and pumping of the soil surface, especially during and soon after periods of wet weather.

If the subgrade cannot be adequately compacted to minimum densities as described above, one of the following measures will be required: 1) removal and replacement with select fill, 2) chemical treatment of the soil to dry and increase the stability of the subgrade, or 3) drying by natural means if the schedule allows.

In our experience with similar soils in this area, chemical treatment is an efficient and effective method to increase the supporting value of wet and weak subgrade. Terracon should be contacted for additional recommendations if chemical treatment of the soils is needed.

Prior to placing any fill, all surface vegetation, topsoil, possible fill material and any otherwise unsuitable materials should be removed from the construction areas. Wet or dry material should either be removed or moisture conditioned and recompacted. After stripping and grubbing, the subgrade should be proof-rolled where possible to aid in locating loose or soft areas. Proof-rolling



can be performed with a 15-ton roller or fully loaded dump truck. Soft, dry and low-density soil should be removed or compacted in place prior to placing fill.

Grading and Drainage

It is important that positive drainage be established during construction such that water will not pond around the structures during or following the construction period.

All grades must be adjusted to provide positive drainage away from the structures. Where paving or flatwork abuts the structures, care should be taken that the joint is properly sealed and maintained. Roof drains should discharge away from the control building.

Earthwork Construction Considerations

Shallow excavations, for the proposed structure, are anticipated to be accomplished with conventional construction equipment. Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of floor slabs. Construction traffic over the completed subgrades should be avoided. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. Water collecting over, or adjacent to construction area should be removed. If the subgrade freezes, desiccates, saturates, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompacted, prior to floor slab construction.

As a minimum, excavations should be performed in accordance with OSHA 29 CFR, Part 1926, Subpart P, "Excavations" and its appendices, and in accordance with any applicable local, and/or state regulations.

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for construction site safety, or the contractor's activities; such responsibility shall neither be implied nor inferred.

Construction Observation and Testing

The earthwork efforts should be monitored under the direction of the Geotechnical Engineer. Monitoring should include documentation of adequate removal of vegetation and top soil, proofrolling and mitigation of areas delineated by the proof-roll to require mitigation.

Each lift of compacted fill should be tested, evaluated, and reworked as necessary until approved by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one test for every 2,500 square feet of



compacted fill in the building area and 5,000 square feet in pavement areas. One density and water content test for every 50 linear feet of compacted utility trench backfill.

In areas of foundation excavations, the bearing subgrade should be evaluated under the direction of the Geotechnical Engineer. In the event unanticipated conditions are encountered, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project provides the continuity to maintain the Geotechnical Engineer's evaluation of subsurface conditions, including assessing variations and associated design changes.

Corrosion Considerations

The table below lists the results of laboratory soluble sulfate, soluble chloride, pH and resistivity testing. The values may be used to estimate potential corrosive characteristics of the on-site soils with respect to contact with the various underground materials which will be used for project construction.

Corrosivity Test Results Summary						
Boring	Sample Depth (feet)	Soil Description	Soluble Sulfate (%)	Soluble Chloride (%)	рН	Resistivity (ohm-cm)
B-3	6 - 8	Fat Clay (CH)	4,817	2,475	7.6	116

Results of soluble sulfate testing indicate samples of the on-site soils tested possess severe sulfate concentrations when classified in accordance with Table 4.3.1 of the ACI Design Manual. Concrete should be designed in accordance with the provisions of the ACI Design Manual, Section 318, Chapter 4. To improve sulfate resistance of concrete in severe sulfate exposure when Type V cement is not available, the following should be considered:

- Use of Type I-II modified cement for sulfate resistance
- Cement should have a tricalcium aluminate content of not more than 8%.
- Concrete mixture should contain at least 20% Class F fly ash.
- Provide air-entrainment of 4% to 7% by volume.
- Lower the water to cement ratio to 0.4 to 0.45.

Thermal Resistivity Testing

A laboratory thermal resistivity (TR) was performed on a remolded specimen of representative soils from the native soils. The bulk sample was recovered from the upper 5 feet of soil in the vicinity of boring B-2. The results of TR testing are included in **Exploration Results**.



Electrical Earth Resistivity Testing (EER)

Terracon performed two (2) field EER survey alignments at location selected by the client following ASTM G-57, using the Four-Electrode Wenner method. The results of EER testing are included in **Exploration Results**.

FOUNDATIONS SYSTEMS

The proposed structures, depending on the load requirements and expected performance, can be supported on a variety of foundations which include drilled piers, mats, and slabs. Near-surface foundations, such as the equipment pads and the slab foundations may be sensitive to movement. If a structure can withstand the anticipated movement presented in this report, then spread footings may be utilized.

A slab foundation would be appropriate for the proposed building-type structures. However, spread footings should not be utilized for buildings or structures sensitive to movement because of the increased risk of differential movement. Thickened and widened sections of the slab could be constructed for areas of concentrated loads.

A deep foundation system, such as drilled piers, would be appropriate to support the structural loads of dead-end structures, and those structures requiring more capacity than a shallow foundation can provide. Recommendations for these types of foundation systems are provided in the following sections, along with other geotechnical considerations for this project.

Design Parameters – Slab-on-Grade Foundation

The foundation design parameters presented below are based on our evaluation using published theoretical and empirical design methods.

These were developed based on our understanding of the proposed project, our interpretation of the information and data collected as a part of this study, our area experience and the results of our evaluation. The structural engineer should select the appropriate slab design method and code for the amount of anticipated slab movement indicated.

The slab-on-grade foundation may be designed using the following parameters provided the subgrade is prepared as outlined in the **Earthwork** and **Floor Slabs** sections of this report:

Item	Description
Select Fill Pad	Minimum 2 feet of select fill over 8 inches of moisture conditioned and compacted on-site soils.

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



ltem	Description
Allowable Bearing Pressure ¹ Compacted select fill	Net Total Load - 2,500 psf
Climatic Rating	15
Design Plasticity Index	24
Soil Support Index	0.90
Estimated PVR ²	About 1 inch
Approximate total settlement ³	About 1 inch
Estimated Differential Settlement ³	Approximately 1/2 of total settlement
Min. perimeter grade beam embedment ⁴	18 inches below finished grade

1. The net allowable bearing pressure provided above include a factor of safety of at least 2.

2. The slab-on-grade foundation system should be designed to tolerate the anticipated soil movement and provide satisfactory support to the proposed structure. The foundation should have adequate exterior and interior grade beams to provide sufficient rigidity to the foundation system such that the slab deflections that result are considered tolerable to the supported structure.

- 3. This estimated post-construction settlement is assuming proper construction practices are followed. Settlement response of a select fill supported slab is influenced more by the quality of construction than by soil-structure interaction. Therefore, it is essential that the recommendations for foundation construction be strictly followed during the construction phases of the building pad and foundation.
- 4. To bear within the select fill or moisture conditioned and recompacted on-site soils. The grade beams may be thickened and widened where necessary to support column loads.

Construction Considerations for Slab-on-Grade Foundation

Excavations for grade beams should be performed with equipment capable of providing a relatively clean bearing area. The bottom 6 inches of the excavations should be completed with a smooth-mouthed bucket or by hand labor. The excavations should be neatly excavated and properly formed. Debris in the bottom of the excavation should be removed prior to reinforcing steel placement. Water should not be allowed to accumulate at the bottom of the excavation. Due to the presence of dry soils, caving of grade beam excavation may occur. Therefore, the foundation contractor should be prepared to use forms.

To reduce the potential for groundwater seepage into the excavations and to minimize disturbance to the bearing area, we recommend that concrete and reinforcing steel be placed as soon as possible after the excavations are completed. Excavations should not be left open for more than 36 hours. The bearing surface of the grade beams should be evaluated after excavation is completed and immediately prior to placing concrete.

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026




Design Recommendations – Spread Footing Foundation

A spread footing foundation system may be used to support some of the planned structures that are not sensitive to movement. On-site clay soils have a moderate to high potential for shrink/swell movements. The PVR of the soils in the general area of the substation is expected to be about 1 to 2 inches. Some industrial structures may not be affected by movements of this magnitude and shallow spread footings might be a cost-effective foundation option.

Spread footings may be considered in the design of the foundations to support the main column loads. Lateral loads transmitted to the footings should be resisted by a combination of soil-concrete friction on the base of the footing and passive pressure on the side of the footing. To resist lateral forces, a net allowable passive resistance may be utilized for portions of footings extending at least 30 inches below finished grade. If the footing is formed during construction, the open space between the footing and the in-situ soils should be backfilled with soils. Also, care should be taken to avoid disturbance of the footing bearing area since loose material could increase settlement and decrease resistance to lateral loading.

The spread footings can provide some uplift resistance for those structures subjected to wind or other induced structural loading.

Uplift resistance of spread footings can be developed from the effective weight of the footing and the overlying soils. As illustrated on the subsequent figure, the effective weight of the soil prism defined by diagonal planes extending up from the top of the perimeter of the foundation to the ground surface at an angle, θ , of 20 degrees from the vertical can be included in uplift resistance. The maximum allowable uplift capacity should be taken as a sum of the effective weight of soil plus the dead weight of the foundation, divided by an appropriate factor of safety. A soil unit weight of 120 pcf should be used for the backfill. This unit weight should be reduced to 58 pcf for portions of the backfill or natural soils below the groundwater elevation.



Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



Design values for the footings are presented below.

Item	Description
Minimum Embedment Below Finished Grade ¹	2½ feet
Net Allowable Bearing Pressure ⁷	Total Load - 2,500 psf
Approximate total settlement ²	About 1 inch
Estimated Differential Settlement ³	Approximately ½ of total settlement
Allowable Passive Pressure ⁴	650 psf (if considered)
Coefficient of Sliding Friction ⁵	0.40
Uplift Resistance ⁶	Foundation Weight (150 pcf) & Soil Weight (120 pcf)

- 1. To bear within the native soils or select fill.
- 2. This estimated post-construction settlement of the shallow footings is without considering the effect of stress distribution from adjacent foundations and assuming proper construction practices are followed. A clear distance between the footings of one footing size should not produce overlapping stress distributions and would essentially behave as independent foundations.
- 3. Differential settlement may result from variances in subsurface conditions, loading conditions and construction procedures. The settlement response of the footings will be more dependent upon the quality of construction than upon the response of the subgrade to the foundation loads. We estimate that the differential settlement should be approximately one-half of the total settlement. Settlement of footings will be more sensitive to installation techniques than to soil-structure interaction.
- 4. The passive pressure along the exterior of the footings should be neglected unless pavement is provided up to the edge of the structure. For interior footings, the allowable passive pressure may be used for the entire depth of the footing. The passive pressure provided above includes a factor of safety of at least 3.
- 5. Lateral loads transmitted to the footings will be resisted by a combination of soil-concrete friction on the base of the footings and passive pressure on the side of the footings.
- 6. The ultimate uplift capacity of shallow footings should be reduced by an appropriate factor of safety to compute allowable uplift capacity.
- 7. The net allowable bearing pressure provided above include a factor of safety of at least 2.

Construction Considerations for Spread Footing Foundations

As noted in **Earthwork**, the footing excavations should be evaluated under the direction of the Geotechnical Engineer. The base of all foundation excavations should be free of water and loose soil, prior to placing concrete. Concrete should be placed soon after excavating to reduce bearing soil disturbance. Care should be taken to prevent wetting or drying of the bearing materials during construction. Excessively wet or dry material or any loose/disturbed material in the bottom of the footing excavations should be removed/reconditioned before foundation concrete is placed. Due to the presence of dry soils, caving of excavation may occur. Therefore, the foundation contractor should be prepared to use forms.

May 18, 2020 - Terracon Project No. 88205026




Excavation should be accomplished with a smooth-mouthed bucket. If a toothed bucket is used, excavation with this bucket should be stopped 6 inches above the final bearing surface and the excavation completed with a smooth-mouthed bucket or by hand labor.

If the footing foundations are over-excavated and formed, the backfill around the foundation sides should be achieved with compacted select fill, lean concrete, compacted cement stabilized sand (two sacks cement to one cubic yard of sand) or flowable fill. Compaction of select fill should be as described later in this section of the report.


The bearing surface should be excavated with a slight slope to create an internal sump for runoff water collection and removal. If surface runoff water in excess of 2 inches accumulates at the bottom of the excavation, it should be pumped out prior to concrete placement. Under no circumstances should water be allowed to adversely affect the quality of the bearing surface. If the spread footing is buried, backfill above the foundation may be the excavated on-site soils or select fill soils. Backfill soils should be compacted to at least 95 percent of the maximum dry density as determined by the standard moisture/density relationship test (ASTM D 698). Moisture contents for on-site soils and imported select fill soils should be within 2 percentage points of the optimum moisture content. The backfill should be placed in thin, loose lifts of about 8 inches, with compacted thickness not to exceed 6 inches.

If unsuitable bearing soils are encountered at the base of the planned footing excavation, the excavation should be extended deeper to suitable soils, and the footings could bear directly on these soils at the lower level or on lean concrete backfill placed in the excavations. This is illustrated on the sketch below.





Over-excavation for structural fill placement below footings should be conducted as shown below. The over-excavation should be backfilled up to the footing base elevation, with select fill placed, as recommended in the Earthwork section.



Design Recommendations – Mat Foundation

A mat foundation may be utilized for some of the structures at the site. The Potential Vertical Rise (PVR) of the soils encountered at the site is about 1 to 2 inches in present condition. Based on the stiffness of a mat foundation, we anticipate that a PVR of about 1 inch, the typical design movement for these types of structures, can be tolerated.

The mat can be designed as a uniform thick concrete member extending above final grade or can be designed as a less thick member with the main mat portion buried and skids extending above final grade to support the structure.

The mat should be analyzed using a soil-structure interaction program to identify areas of high contact stresses, excessive movements and large moments. The subgrade and select fill soils should be prepared as outlined in the **Earthwork** section of this report, which contains material and placement requirements for select fill, as well as other subgrade preparation recommendations.

Item	Description
Select Fill Pad	As needed (Min. 2 feet)
Minimum Mat Embedment Depth ¹	8 inches below final grade
Maximum Contact Pressures	2,500 psf
Modulus of Subgrade Reaction	75 pounds per cubic inch (pci)
Soil Unit Weight ²	100 pounds per cubic foot (pcf)
Estimated PVR ³	About 1 inch

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



Item	Description
Approximate total settlement ⁴	About 1 inch
Estimated differential settlement ⁴	Approximately ½ of total settlement

- 1. To bear within the select fill.
- 2. A buried mat would provide more resistance to uplift than the uniform thick mat since the weight of the soil overlying the mat would also be included in the uplift resistance computations. In addition to the weight of foundation and structure, any soil directly overlying the foundation may also be considered. The soil unit weight provided above may be assumed for the on-site soils placed above the footing, provided the fill is properly compacted.
- 3. The buried mat foundation system should be designed to tolerate the anticipated soil movement and provide satisfactory support to the proposed structures.
- 4. This estimated post-construction settlement is assuming proper construction practices are followed.

Construction Considerations for Mat Foundations

Excavations for a mat foundation should be performed with equipment capable of providing a relatively clean bearing area. The bottom 6 inches of the excavations should be completed with a smooth-mouthed bucket or by hand labor.

The excavations should be neatly excavated and properly formed. If neat excavation is not possible then the foundation should be over-excavated and formed. All loose materials should be removed from the over-excavated areas and filled with lean concrete, compacted cement stabilized sand (two sacks cement to one cubic yard of sand) or flowable fill (ACI-229R).

Steel should be placed and the foundation poured the same day of excavation. If not, a seal slab consisting of lean concrete should be poured on the same day the contractor achieves the final bearing level in order to protect the exposed foundation soils. The bearing surface should be excavated with a slight slope to create an internal sump for runoff water collection and removal. If surface runoff water in excess of 2 inches accumulates at the bottom of the excavation, it should be pumped out prior to concrete placement. Under no circumstances should water be allowed to adversely affect the quality of the bearing surface.

The bearing surface of the foundation should be evaluated after excavation is completed and immediately prior to placing concrete.

Design Parameters - Drilled Pier Foundation

Axial compressive loads for the structures may be supported on straight-sided (non-underreamed) piers. Due to the presence of subsurface water at relatively shallow depth, under-reamed drilled piers should not be considered for this site.



For the purposes of evaluating the subsoils for use in foundation analyses, we have developed soil parameters for axial capacity analysis for foundation design which are provided in **Exploration Results**.

Straight-sided drilled pier foundations may be designed using the following equations to evaluate the pier foundation sizes for both compressive and tensile (uplift) axial loading:

Ultimate skin friction capacity ^{1,5}	$Q_s = \pi d (f_s)(h)$
Ultimate end bearing capacity ^{1,5}	$Q_b=0.25\pi d^2(q_{eb})$
Ultimate pier capacity in compression ⁵	$Q_c = Q_s + Q_b$
Ultimate pier capacity in tension (uplift) ^{1,5}	$Q_t = \pi d (f_s)(h)(R)+W$
Ultimate skin friction ^{2,4}	$f_s = \alpha C_u$
Ultimate skin friction ^{3,4}	$f_s = \sigma' Ktan \delta$
Ultimate end bearing pressure ^{2,4}	$q_{eb} = c_u N_c$
Ultimate end bearing pressure ^{3,4}	$q_{eb} = \sigma' N_q$
Estimated uplift pressure (kips) ¹⁰	Up = 5 • d
Ultimate uplift resistance (kips) ^{1,6}	$Q_r = 2.0 \bullet d(ft.) \bullet h(ft.) + W(kips) + P_{DL}(kips)$
Minimum percentage of steel ⁷	As required by structural engineer
Maximum embedment depth	45 feet below existing grade
Approximate total settlement ⁸	About 1 inch
Estimated differential settlement ⁹	Approximately 1/2 of total settlement

- 1. Definitions: d = pier diameter; h = pier segment length; R = uplift reduction factor (equal to 0.7 for sands, 0.9 for clays); W = effective weight of the pier foundation; P_{DL} = dead load acting on the drilled pier
- 2. Ultimate value for cohesive soils only.
- 3. Ultimate value for cohesionless soils only.
- 4. Soil parameters provided in Exploration Results: α = skin friction adhesion factor (strength reduction factor). (equal to zero with the top 5 feet and one shaft diameter of the base of the pier); c_u = undrained shear strength of the soil; N_c = end bearing capacity factor for clay soil; σ' = effective overburden pressure; K = horizontal stress coefficient; δ = soil to pier friction angle (equal to soil angle of internal friction (ϕ) for concrete piers); N_q = end bearing capacity factor for granular soils
- 5. A factor of safety of 3 should be applied to ultimate end bearing, 2 to side shear (skin friction), and 2 to uplift (tension).
- 6. A factor of safety of at least 2 should be applied to the computed ultimate uplift force.
- 7. The piers should contain sufficient vertical reinforcing steel throughout the entire shaft length to resist uplift (tensile) forces due to post-construction heave of the clay soils. The amount of reinforcing steel required can be computed by assuming that the dead load of the structure surcharges the pier and that the above estimated tensile force acts vertically on the shaft.
- Provided proper construction practices are followed. A clear distance between the piers of three times the pier diameter should be provided to develop the recommended bearing pressures and to control settlements. If this clearance cannot be maintained in every case,

Terracon should be contacted so that we may determine the reduced capacities. Settlements provided for single, isolated piers/piles only.

9. Will result from variances in subsurface conditions, loading conditions and construction procedures, such a



cleanliness of the bearing area or flowing water in the shaft. Settlements provided for for single, isolated piers only.

10. U_p = uplift load, kips; d = shaft diameter, feet.

Drilled Pier Lateral Loading

<u>Lateral Loading</u>: The proposed structure(s) supported on drilled piers may be subject to lateral loading, the criteria for lateral load analysis is presented in **Exploration Results** are for use with the computer programs LPILE and FAD Tools. Several methods, including hand solutions and computer programs, are available for calculating the lateral behavior of piles and drilled piers. Most of these methods rely on "key" soil parameters such as soil elastic properties (E and ks), strain at 50 percent of the principal stress difference (ε 50), undrained shear strength (c), and load-deflection (p-y) criteria. The p-y criteria, which are commonly used to model soil reaction, were developed from instrumented load tests and are generally considered to provide the best model of soil behavior under short-term lateral loading.

The foundations will need to be designed to resist high loads due to the structure height and the imposed forces from wind loading. Generally, four (4) load cases are applied to this type of structures; axial compressive loading, axial uplift (tensile) loading, lateral loading, and rotational. The foundations experience high lateral and rotational loading, which nearly always controls the foundation design. Axial loading of the foundation is relatively low and seldom controls the foundation design. However, the foundation should always be analyzed for the four (4) load cases to establish the controlling load case.

Factors of safety are not generally applied to the lateral load analysis. A performance criterion, or "limit state", are usually considered. For most foundations subjected to lateral loads, the pier foundation is designed with a limit of 1 inch of deflection at the top of the pier and 1 degree of rotation as measured from the vertical axis of the pier. The analysis is generally conducted using the working loads and the limit state values. The applied loads are then doubled to evaluate the deflection and rotation at the top of the pier to determine if the foundation will topple over under extreme overload. This overload condition may indicate that the foundation would deflect or rotate such that the structure(s) will tilt, but the foundation will not experience failure. Structural limits, such as moment capacity and shear, may control the design and should be evaluated by the Structural Engineer.

Construction Considerations for Drilled Pier Foundation

Drilled excavations to a maximum depth of 45 feet below existing grade (grade at the time of our field activities) may be performed for installation of the drilled piers for the proposed structures at this site.



Groundwater was observed in the borings between 7 and 34 feet bgs during drilling operations and after drilling activities. Depending on weather conditions, groundwater levels may vary from the levels observed during our field program. Water must not be allowed to accumulate in the bottom of the pier excavations.

As previously discussed, subsurface water and sand soils were observed within the explored depths in the borings. Sloughing is likely to occur below the subsurface water table during construction. Therefore, the contractor should be prepared to remove water from the drilled piers if necessary. We recommend that slurry or casing drilling techniques be used to control sloughing of the subsurface soils during pier construction. Casing should only be used in drilled piers terminating in the Clay soils. Slurry drilling techniques are appropriate for piers terminating in all soil types encountered in the borings.

<u>Slurry Method-</u> Water or a weighted drilling fluid may be considered to install the pier foundations. Slurry displacement drilling can only prevent sloughing and water influx but cannot control sloughing once it has occurred. Therefore, slurry displacement drilling techniques must begin at the ground surface, not after sloughing materials are encountered.

Typical drilling fluids include those which contain polymers or bentonite. If a polymer is used with "hard" mixing water, a water softening agent may be required to achieve intimate mixing and the appropriate viscosity. The polymer manufacturer should be consulted concerning proper use of the polymer. If bentonite slurry is used, the bentonite should be mixed with water several hours before placing in the pier excavation. Prior mixing gives the bentonite sufficient time to hydrate properly. The drilling fluid should only be of sufficient viscosity to control sloughing of the excavation walls and subsurface water flow into the excavation.

Care should be exercised while extracting the auger so that suction does not develop and cause disturbance or create "necking" in the excavation walls as described above. Casing should not be employed in conjunction with the slurry drilling technique due to possible trapping of loose soils and slurry between the concrete and natural soil.

The use of weighted drilling fluid when installing drilled pier foundations requires extra effort to ensure an adequate bearing surface is obtained. A clean-out bucket should be used just prior to pier completion in order to remove any cuttings and loose soils which may have accumulated in the bottom of the excavation. Reinforcing steel and concrete should be placed in the excavation immediately after pier completion. A closed-end tremie should be used to place the concrete completely to the bottom of the excavation in a controlled manner to effectively displace the slurry during concrete placement.



When the pier excavation depth is achieved, and the bearing area has been cleaned, steel and concrete should then be placed immediately in the excavation. The concrete should be placed completely to the bottom of the excavation with a closed-end tremie in the pier excavation if more than 3 inches of water is ponded on the bearing surface or the slurry drilling technique is used. A short tremie may be used if the excavation has less than 3 inches of ponded water or if the water is pumped out prior to concrete placement. The fluid concrete should not be allowed to strike the pier reinforcement, temporary casing (if required) or excavation sidewalls during concrete placement.

Casing Method - Casing will provide stability of the excavation walls and will reduce water influx; however, casing may not completely eliminate subsurface water influx potential. In order for the casing to be effective, a "water tight" seal must be achieved between the casing and surrounding soils. The drilling subcontractor should determine casing depths and casing procedures. Water that accumulates in excess of 3 inches in the bottom of the pier excavation should be pumped out prior to reinforcing steel and concrete placement. If the water is not pumped out, a closed-end tremie should be used to place the concrete completely to the bottom of the pier excavation in a controlled manner to effectively displace the water during concrete placement. If water is not a factor, concrete should be placed with a short tremie so the concrete is directed to the bottom of the pier excavation. The concrete should not be allowed to ricochet off the walls of the pier excavation nor off the reinforcing steel. If this operation is not successful or to the satisfaction of the foundation contractor, the pier excavation should be flooded with fresh water to offset the differential water pressure caused by the unbalanced water levels inside and outside of the casing. The concrete should be tremied completely to the bottom of the excavation with a closed-end tremie.

Removal of casing should be performed with extreme care and under proper supervision to reduce mixing of the surrounding soil and water with the fresh concrete. Rapid withdrawal of casing or the auger may develop suction that could cause the soil to intrude into the excavation. An insufficient head of concrete in the casing during its withdrawal could also allow the soils to intrude into the wet concrete. Both of these conditions may induce "necking", a section of reduced diameter, in the pier.

All aspects of concrete design and placement should comply with the American Concrete Institute (ACI) 318-08 Code Building Code Requirements for Structural Concrete; ACI 336.1-01 entitled Reference Specification for the Construction of Drilled Piers, and ACI 336.3R-93 (Reapproved 2006) entitled Design and Construction of Drilled Piers. Concrete should be designed to achieve the specified 28-day strength when placed at a 7-inch slump with a ± 1 inch tolerance. Adding



water to a mix that has been designed for a lower slump does not meet the intent of this recommendation. If a high range water reducer is used to achieve this slump, the span of slump retention for the specific admixture under consideration should be thoroughly investigated. Compatibility with other concrete admixtures should also be considered. A technical representative of the admixture supplier should be consulted on these matters.

Concrete aggregates in the area could have a history of problems associated with Alkali Silica Reactivity (ASR). If aggregates are known to have a history of ASR, then one of the following should be incorporated in the concrete used for the foundations:

- Option 1: Replace 20 to 35% of the cement with Class C or Class F fly ash. However, if sulfate resistant concrete is required, do not use a Class C fly ash and do not use Type I Portland cement.
- Option 2: Use a lithium nitrate admixture at a minimum dosage of 0.55 gallons of 30% lithium nitrate solution per pound of alkalies present in the portland cement. Coordinate with admixture supplier.
- Option 3: When using portland cement only, ensure that the total alkali contribution from the cement in the concrete does not exceed 4.00 lb. per cubic yard of concrete when calculated as follows:

Pounds of alkali per cu yd. = (pounds of cement per cu yd) x (%Na2O equivalent in cement)/100.

In the above calculation, use the maximum cement alkali content reported on the cement mill certificate.

Option 4: Test both coarse and fine aggregate separately, in accordance with ASTM C 1260, using 440g of the proposed cementitious material in the same proportions of portland cement to supplementary cementing material to be used in the mix. Before use of the mix, provide the certified test report, signed and sealed by a licensed professional engineer, demonstrating that the ASTM C 1260 test result for each aggregate does not exceed 0.10% expansion.

Successful installation of drilled piers is a coordinated effort involving the general contractor, design consultants, subcontractors and suppliers. Each must be properly equipped and prepared to provide their services in a timely fashion. Several key items of major concern are:

- Proper drilling rig with proper equipment (including casing and augers);
- Reinforcing steel cages tied to meet project specifications;
- Proper scheduling and ordering of concrete for the piers; and

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



Monitoring of installation by design professionals.

Pier construction should be carefully monitored to assure compliance of construction activities with the appropriate specifications. Particular attention to the referenced publication is warranted for pier installation. A number of items of concern for pier installation include those listed below.

- Pier locations
- Vertical alignment
- Competent bearing
- Reinforcement steel placement
- Concrete properties and placement
- Proper casing seal for groundwater control
- Slurry viscosity
- Casing removal

If the contractor has to deviate from the recommended foundations, Terracon should be notified immediately so additional engineering recommendations can be provided for an appropriate foundation type.

SEISMIC CONSIDERATIONS

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7 and the International Building Code (IBC). Based on the soil properties encountered at the site and as described on the exploration logs and results, it is our professional opinion that the **Seismic Site Classification is D**. Subsurface explorations at this site were extended to a maximum depth of 50 feet. The site properties below the boring depth to 100 feet were estimated based on our experience and knowledge of geologic conditions of the general area. Additional deeper borings or geophysical testing may be performed to confirm the conditions below the current boring depth.

FLOOR SLABS

Floor Slab Design Parameters

The subsurface soils at this site generally exhibit moderate to high expansion potential. Based on the information developed from our field and laboratory programs and on method TEX-124-E in the Texas Department of Transportation (TxDOT) Manual of Testing Procedures, we estimate



that the subgrade soils at this site exhibit a Potential Vertical Rise (PVR) of about 1 to 2 inches in present condition.

The actual movements could be greater if poor drainage, ponded water, and/or other sources of moisture are allowed to infiltrate beneath the structure after construction. We have provided recommendations to reduce the site PVR to about 1 inch. In addition, positive structure perimeter drainage should be carefully observed.

After site stripping and over-excavation activities as recommended, re-used on-site soil (that meet select fill criteria) or select fill over 8 inches of moisture conditioned and compacted subgrade soils should be constructed directly below the floor slab and should also extend a minimum of 3 feet beyond the edge of the proposed building area, including any movement sensitive flatwork that abuts the structure such as sidewalks. The final exterior grade adjacent to the building should be sloped to promote positive drainage away from the structure.

The subgrade and select fill soils should be prepared as outlined in the **Earthwork** section of this report, which contains material and placement requirements for select fill, as well as other subgrade preparation recommendations. The floor slab should be designed using the following recommendations.

Item	Description
Excavation	Minimum 6 inches.
Floor Slab Support ¹	Min. 8 inches of moisture conditioned and compacted native soils plus 2 feet of select fill (plus additional if needed to achieve Finished Pad Elevation).
Estimated Modulus of Subgrade Reaction ²	100 pounds per square inch per inch (psi/in) for point loads.
Estimated Potential Vertical Rise (PVR)	About 1 inch

1. Floor slabs should be structurally independent of building footings or walls to reduce the possibility of floor slab cracking caused by differential movements between the slab and foundation. This recommendation applies to building area and movement-sensitive flatwork that abuts the structure.

2. Modulus of subgrade reaction is an estimated value based upon our experience with the subgrade condition, the requirements noted in Earthwork, and the floor slab support as noted in this table. It is provided for point loads. For large area loads the modulus of subgrade reaction would be lower.

Floor Slab Construction Considerations

Finished subgrade within and for at least 10 feet beyond the floor slab should be protected from traffic, rutting, or other disturbance and maintained in a relatively moist condition until floor slabs are constructed. If the subgrade should become damaged or desiccated prior to construction of floor slabs, the affected material should be removed and structural fill should be added to replace the



resulting excavation. Final conditioning of the finished subgrade should be performed immediately prior to placement of the floor slab support course.

The Geotechnical Engineer should approve the condition of the floor slab subgrades immediately prior to placement of the floor slab support course, reinforcing steel and concrete. Attention should be paid to high traffic areas that were rutted and disturbed earlier, and to areas where backfilled trenches are located.

GENERAL COMMENTS

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Natural variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence or collaboration through this system are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client, and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly impact excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety, and cost estimating including, excavation support, and dewatering requirements/design are the responsibility of others. If changes in the nature, design, or location

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

ATTACHMENTS

Responsive Resourceful Reliable



EXPLORATION AND TESTING PROCEDURES

Field Exploration

Number of Borings	Boring Depth (feet) ¹	Location
3	50	Proposed Structures
1. Below ground surface		

Boring Layout and Elevations: Terracon personnel provided the boring layout. Coordinates were obtained with a handheld GPS unit (estimated horizontal accuracy of about ±10 feet).

Subsurface Exploration Procedures: We advanced the soil borings with a truck-mounted drill rig using continuous flight augers (solid stem and/or hollow stem as necessary depending on soil conditions). Five samples were obtained in the upper 10 feet of the borings and at intervals of 5 feet thereafter. Soil sampling was performed using thin-wall tube and/or split-barrel sampling procedures. We observed and recorded groundwater levels during drilling and sampling. For safety purposes, the borings were backfilled with cement-bentonite grout after their completion.

The sampling depths, penetration distances, and other sampling information were recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a geotechnical engineer. Our exploration team prepared field boring logs as part of the drilling operations. The field logs included visual classifications of the materials encountered during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field log. The final boring logs represent the geotechnical engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Laboratory Testing

The project engineer reviewed the field data and assigned various laboratory tests to better understand the engineering properties of the various soil strata as necessary for this project.

- ASTM D2216 Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
- ASTM D4318 Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
- ASTM D422 Standard Test Method for Particle-Size Analysis of Soils
- ASTM D2166/D2166M Standard Test Method for Unconfined Compressive Strength of Cohesive Soil

Geotechnical Engineering Report

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026



- ASTM D4546 Standard Test Methods for One-Dimensional Swell or Collapse of Soils
- ASTM D512 Standard Test Methods for Chloride Ion in Water
- ASTM C1580 Standard Test Method for Water-Soluble Sulfate in Soil
- ASTM G 51 Standard Test Method for pH of Soils

The laboratory testing program often included examination of soil samples by an engineer. Based on the material's texture and plasticity, we described and classified the soil samples in accordance with the Unified Soil Classification System (USCS).

SITE LOCATION AND EXPLORATION PLANS

Contents:

Site Location Plan Exploration Plan

SITE LOCATION

Airport Distribution Substation
Brownsville, Texas
May 18, 2020
Terracon Project No. 88205026






DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

MAP PROVIDED BY MICROSOFT BING MAPS

EXPLORATION PLAN

Airport Distribution Substation Brownsville, Texas May 18, 2020 Terracon Project No. 88205026






DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

MAP PROVIDED BY MICROSOFT BING MAPS

EXPLORATION RESULTS

Contents:

Boring Logs GeoModel Thermal Resistivity Test Results Electrical Earth Resistivity Test Results Lateral and Axial Design Parameters for Undrained Condition

BORING LOG NO. B-1

Page 1 of 1


PROJ	ECT: Airport Distribution Substation		С	LIE	NT:		rownsville Public Utilities Board rownsville, TX						
SITE:	Billy Mitchel Blvd and S. Central A Brownsville, TX	venue											
gg ER	LOCATION See Exploration Plan		ī	NS	ΡE	F	STR	ENGTH	TEST	(%	3f)	ATTERBERG LIMITS	U U
MODEL LAYER GRAPHIC LOG	Latitude: 25.9065° Longitude: -97.4476° DEPTH	DEPTH (Ft.)		WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	TEST TYPE	COMPRESSIVE STRENGTH (tsf)	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	LL-PL-PI	
	FAT CLAY (CH), dark grayish brown to light br stiff to hard	rown,	_		X	3-5-6 N=11				21			
			_		\times	4-5-6 N=11				27		58-20-38	
		5	-	▼		1.5 (HP) 1.5 (HP)		0.81	10	23 22	105		8
	- with non-plastic Sandy Silt (ML) seams at 8	feet 10				SAMPLE DISTURBED		0.01	10	23	100	NP	
			_										
	- sandy at 13½ feet	15	5-		X	2-4-6 N=10				18			6
			_			1.5 (HP)		1.90	10	20	110		
		20)										
1		25	5-			4.5 (HP)				24		77-25-52	ę
			_										
		30)			3.5 (HP)		2.58	8	30	95		
		35		∇		4.5+ (HP)				32			
		40	- - - -			3.75 (HP)				27		72-27-45	
			-										
		45	5-			4.5 (HP)		2.59	4.2	28	95		
	- with Silty Sand (SM) seams at 48 feet 50.0		-			SAMPLE DISTURBED				24			
	Boring Terminated at 50 Feet	50)			DISTORDED							
0	atification lines are approximate. In situ, the transition start is					Homes	r T	Autors	atic				
	atification lines are approximate. In-situ, the transition may be g	grauuai.					туре	e: Autom	auC				
	ent Method: See description depth. See used	Exploration and Te ription of field and I and additional data	<mark>sting</mark> labor a (lf a	<mark>Proc</mark> ratory any).	edure proc	es for a Notes: edures							
	ent Method: symbolic	Supporting Informa pols and abbreviation		for ex	plana	ation of							
						Boring Sta	arted:	04-16-20	20	Borir	ng Com	pleted: 04-16-	-202
	hile drilling ter 15 minutes	llerr	_			Drill Rig: 0	CME-7	75		Drille	er: Envir	roCore	
7.01	completion of drilling	1506 Mid Phar				Project No	o.: 882	205026					

BORING LOG NO. B-2

Page 1 of 1

PROJE	ECT: Airport Distribution Substatior	ı	0	CLIE	NT:	Brownsville Brownsville			ilities	s Boa	ard		
SITE:	Billy Mitchel Blvd and S. Centra Brownsville, TX	al Avenue											
MODEL LAYER GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 25.9062° Longitude: -97.4473° DEPTH		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	TEST TYPE	COMPRESSIVE D STRENGTH D (tsf) H	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	Atterberg Limits LL-PL-PI	DEPCENT EINES
	FAT CLAY (CH), dark gray, medium stiff t Lean Clay (CL) seams to 2 feet	to stiff, with	-	-	\ge	3-5-6 N=11 1.5 (HP))			27 19		48-19-29	9
			5 -			0.5 (HP) 0.5 (HP)	-	0.48	10	34 48	73	50-22-28	
1			- - 10- -			1.25 (HP)	-			40		98-33-65	ç
			- - 15-			2.0 (HP)	-	1.53	9	30	92		
	20.0 SILTY SAND (SM), brown, medium dense	e to dense	- - - 20-	-	X	3-5-6 N=11	_			33			
		2	- - 25-	-	X	5-7-12 N=19	_			28			3
2			- - 30-	-	X	6-12-18 N=30	-			26			
	- with Poorly Graded Sand with Silt (SP-S 35.0 33½ feet FAT CLAY (CH), reddish brown, very stiff		- - 35	-	X	7-18-19 N=37	-			25			
		2	- - 40- -	-	X	7-8-11 N=19	/			29		66-21-45	-
		2	- - 45-	-		4.5+ (HP)	-	2.96	6.3	26	95		
	50.0 Boring Terminated at 50 Feet	į	- - 50-	-		4.25 (HP)	-			23			
Advanceme	atification lines are approximate. In-situ, the transition ma nt Method: em augered to termination depth.	y be gradual. See Exploration and description of field an used and additional d	nd lab	oratory	cedure v proce	es for a Notes:	er Type	e: Autom	atic				
Abandonme Boring ba completic	ackfilled with cement-bentonite grout upon	See Supporting Inform symbols and abbrevia	matio	n for ex	kplana	ition of							
V Wł	WATER LEVEL OBSERVATIONS nile drilling	Jlerr				Boring S Drill Rig:			20	_	ıg Comj er: Envir	pleted: 04-16-	202
_	er 15 minutes completion of drilling	1506 N		ities D		Project N							

		B	ORING LO	C	NC). B-3					F	Page 1 of	1
F	PROJ	ECT: Airport Distribution Substation		CLIE	NT:	Brownsville Brownsville			ilitie	s Boa	ard		
S	SITE:	Billy Mitchel Blvd and S. Central Brownsville, TX	Avenue				,						
ſĒŖ	00	LOCATION See Exploration Plan		/EL	ТҮРЕ	T C	STF	RENGTH	TEST	(%)	cf)	ATTERBERG LIMITS	NES
MODEL LAYER	GRAPHIC LOG	Latitude: 25.9061° Longitude: -97.4475° DEPTH	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TY	FIELD TEST RESULTS	TEST TYPE	COMPRESSIVE STRENGTH (tsf)	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	LL-PL-PI	PERCENT FINES
		FAT CLAY (CH), dark gray to brown and gra - with very stiff to stiff Lean Clay (CL) seams	y, soft to 4 feet	_		9-9-11 N=20				22			
				_	\ge	4-3-5 N=8	1			20		35-16-19	
			5	_	\ge	1-1-2 N=3	1			40			89
					\leq	0-2-1 N=3	1			25			
1			10	-	\bowtie	1-1-1 N=2	1			38		99-31-68	
			15	-	\leq	0-0-2 N=2	_			25			
		18.0 SILTY SAND (SM), brown, loose to very den	se	_		9-16-20	-			28			22
			20	_	\cap	N=36				20			22
				_									
2			25	_	\bowtie	2-3-6 N=9				27			
2				_	ľ								
			30	-		8-12-38	-			23			
			30	_	\square	N=50	1						
				-		4.5.0							
		35.0 FAT CLAY (CH), reddish brown, stiff	35	_	X	4-5-6 N=11				24			19
				_									
			40	_	\bowtie	4-3-5 N=8				29		57-24-33	
				_		IN-0	1						
1				_		3-4-5	_			29			98
			45	_	\cap	N=9				29			90
5				_									
		with Lean Clay (CL) seams at 48½ feet 50.0 Boring Terminated at 50 Feet	50	-	\bowtie	5-6-8 N=14				23		35-18-17	
5		Boring reminated at 50 Feet											
	 Str	atification lines are approximate. In-situ, the transition may be	e gradual.			Hamm	l Ier Typ	e: Auton	natic				
Adv		tem augered to termination depth. de:	e Exploration and Tes scription of field and la ed and additional data	aborator	y proc								
Ε		ent Method: syr ackfilled with cement-bentonite grout upon	e Supporting Informat nbols and abbreviatio		xplana	ition of							
		WATER LEVEL OBSERVATIONS				Boring S	tarted:	04-16-20	20	Borir	ng Com	pleted: 04-16-	2020
	7	hile drilling	llerra								er: Envii		
	_ /	ter 15 minutes completion of drilling	1506 Mid Phari	Cities D		Project I							



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description
1	CLAY	Fat Clay (CH) Soft to hard
2	SAND	Silty Sand (SM) Loose to very dense

Fat Clay

Silty Sand

✓ First Water Observation

V Second Water Observation

Third Water Observation

Groundwater levels are temporal. The levels shown are representative of the date and time of our exploration. Significant changes are possible over time. Water levels shown are as measured during and/or after drilling. In some cases, boring advancement methods mask the presence/absence of groundwater. See individual logs for details. NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

LEGEND



21239 FM529 Rd., Bldg. F Cypress, TX 77433 Tel: 281-985-9344 Fax: 832-427-1752 <u>info@geothermusa.com</u> http://www.geothermusa.com

May 5, 2020

Terracon Consultants 1506 Mid Cities Drive Pharr, Texas 78577 <u>Attn: Stephany Chacon, E.I.T.</u>

Re: Thermal Analysis of Native Soil Sample <u>Airport Distribution Substation – Brownsville, TX (Project No. 88205026)</u>

The following is the report of thermal dryout characterization tests conducted on one (1) sample of native soil from the referenced project sent to our laboratory.

<u>Thermal Resistivity Tests</u>: The sample was compacted at its 'optimum' moisture content and at 95% of the maximum dry density *provided by Terracon*. The tests were conducted in accordance with the IEEE standard 442-2017. The results are tabulated below and the thermal dry out curve is presented in **Figure 1**.

Sample ID, Description, Thermal Resistivity, Moisture Content and Density

Sample ID @ 0' – 5'	Description (Terracon)	Thermal Ro (°C-cn	•	Moisture Content	Dry Density
@ 0 - 5	(Terracon)	Wet	Dry	(%)	(lb/ft ³)
B-2	Lean Clay (CL) w/ Sand	106	202	17	97


<u>Comments</u>: The thermal characteristic depicted in the dry out curve applies for the soil at its respective test dry density.

Please contact us if you have any questions or if we can be of further assistance.

Geotherm USA

Nimesh Patel








Figure 1



		ELECTRI	CALEARTH	RESISTIVITY TES	STING			
Project Nan	ne: Airpo	rt Distribution Sub	station	Manufacturer:		AEMC		
Project No.	:	88205026		Model No.:		4620		
Date:		4/16/2020		Calibration Date	e: 3/9,	9/2020 - 3/9/2021		
Personnel:		David Portillo						
RAVERSE	1 (NORTHEAS	T-SOUTHWEST)		Location: 2	25.906148, -97.4771	00		
Test No.	A Spacing (feet)	Meter Reading	Scale	Resistance Apparent	Multiplier	Earth Resistivity OHM-CM		
1	2.5	1.28	1	1.28	479	613		
2	5	0.22	1	0.22	958	211		
3	10	0.08	1	0.08	1,915	153		
4	20	0.03	1	0.03	3,830	115		
5	40	0.01	1	0.01	7,660	77		
-		a" spacing of 40 feet	were not ob		25.906756, -97.4472	89		
Test No.	A Spacing (feet)	Meter Reading	Scale Ω	Resistance Apparent	Multiplier	Earth Resistivity OHM-CM		
1	2.5	4.47	1	4.47	479	2,140		
2	5	0.73	1	0.73	958	699		
3	10	0.12	1	0.12	1,915	230		
4	20	0.04	1	0.04	3,830	153		
5	40	0.01	1	0.01	7,660	77		
			1					
Cignificant	andings keyend "	a" spacing of 40 feet		tainad				

AXIAL CAPACITY ANALYSES DESIGN SOIL PARAMETERS FOR <u>UNDRAINED CONDITIONS</u> Airport Distribution Substation Brownsville, Texas

		Depth to Bottom of	Effective Unit	Undrained Shear	Adhesion	Friction	Horizontal Stress	Bearin	g Capacity F	actors
	Soil	Soil Layer	Weight	Strength	Factor	Angle	Coefficient	N _c ⁴	N _q	Ng
_	Layer	(feet)	(pcf)	(psf)	(-)	(degrees)	(-)	(-)	(-)	(-)
	1	10	115	1,000	0.72	0		6	1	0
	2	20	56	1,500	0.58	0		6	1	0
	3	50	60	2,500	0.44	0		9	1	0
I	NOTES:									

1. Design depth to subsurface water is about 10 feet.

2. For uplift conditions, the computed skin friction should be multiplied by 0.7 for sands and 0.9 for clay.

3. The unit allowable end bearing should not exceed 100 kips per square foot.

4. The N_c value of 9 for non-granular soils is for D/B ratios greater than 4. Otherwise, use N_c = 6.

AXIAL CAPACITY ANALYSES DESIGN SOIL PARAMETERS FOR UNDRAINED CONDITIONS Airport Distribution Substation Brownsville, Texas

	Depth to	Effective	Undrained	A		Horizontal	Dereit		
	Bottom of	Unit	Shear	Adhesion	Friction	Stress		g Capacity I	-actors
Soil	Soil Layer	Weight	Strength	Factor	Angle	Coefficient	N _c ⁴	N _q	Ng
Layer	(feet)	(pcf)	(psf)	(-)	(degrees)	(-)	(-)	(-)	(-)
1	4	115	1,000		0		6	1	0
2	10	107	500	1.00	0		6	1	0
3	20	56	1,500	0.58	0		6	1	0
4	28	60	0		33	0.75	39	26	35
5	35	66	0		35	0.75	46	33	48
6	50	63	3,000	0.40	0		9	1	0
NOTEO									

NOTES:

1. Design depth to subsurface water is about 10 feet.

2. For uplift conditions, the computed skin friction should be multiplied by 0.7 for sands and 0.9 for clay.

3. The unit allowable end bearing should not exceed 100 kips per square foot.

4. The N_c value of 9 for non-granular soils is for D/B ratios greater than 4. Otherwise, use $N_c = 6$.

AXIAL CAPACITY ANALYSES DESIGN SOIL PARAMETERS FOR <u>UNDRAINED CONDITIONS</u> Airport Distribution Substation Brownsville, Texas

	Depth to	Effective	Undrained			Horizontal			
	Bottom of	Unit	Shear	Adhesion	Friction	Stress	Bearing	g Capacity I	actors
Soil	Soil Layer	Weight	Strength	Factor	Angle	Coefficient	N_{c}^{4}	N _q	Ng
Layer	(feet)	(pcf)	(psf)	(-)	(degrees)	(-)	(-)	(-)	(-)
1	4	115	1,000		0		6	1	0
2	8	107	400	1.00	0		6	1	0
3	18	43	250	1.00	0		6	1	0
4	25	56	0		31	0.75	33	21	26
5	35	60	0		33	0.75	39	26	35
6	50	56	1,500	0.58	0		9	1	0
NOTES:									

1. Design depth to subsurface water is about 8 feet.

2. For uplift conditions, the computed skin friction should be multiplied by 0.7 for sands and 0.9 for clay.

3. The unit allowable end bearing should not exceed 100 kips per square foot.

4. The N_c value of 9 for non-granular soils is for D/B ratios greater than 4. Otherwise, use N_c = 6.

LATERAL CAPACITY ANALYSES DESIGN SOIL PARAMETERS FOR <u>UNDRAINED CONDITIONS</u> Airport Distribution Substation

Brownsville, Texas

				LPILE				LPILE	Μ	FAD
			0.11	Soil	Effective	Undrained	Internal	Soil	Strength	
		Depth to	Soil Layer	Modulus	Unit	Shear	Friction	Strain	Reduction	Deformation
Soil	LPILE	Тор	Bottom	k	Weight	Strength	Angle	Factor	Factor	Modulus
Layer	Soil Type	(feet)	(feet)	(pci)	(pcf)	(psf)	(degrees)	e ₅₀	()	(ksi)
1	Stiff Clay without Free Water	0	10	428	115	1,000	0	0.010	0.72	0.60
2	Stiff Clay without Free Water	10	20	525	56	1,500	0	0.008	0.58	0.90
3	Stiff Clay without Free Water	20	50	718	60	2,500	0	0.006	0.44	1.50

NOTES:

1. Design depth to subsurface water is about 10 feet.

2. MFAD deformation moduli values based on *MFAD 5.1 User Guide, October 2010*

LATERAL CAPACITY ANALYSES DESIGN SOIL PARAMETERS FOR <u>UNDRAINED CONDITIONS</u> Airport Distribution Substation

Brownsville, Texas

		Depth to	Soil Layer	LPILE Soil Modulus	Effective Unit	Undrained Shear	Internal Friction	LPILE Soil Strain	Strength	FAD Deformation
Soil	LPILE	Тор	Bottom	k	Weight	Strength	Angle	Factor	Factor	Modulus
Layer	Soil Type	(feet)	(feet)	(pci)	(pcf)	(psf)	(degrees)	e ₅₀	()	(ksi)
1	Stiff Clay without Free Water	0	4	428	115	1,000	0	0.010		0.60
2	Stiff Clay without Free Water	4	10	332	107	500	0	0.015	1.00	0.30
3	Stiff Clay without Free Water	10	20	525	56	1,500	0	0.008	0.58	0.90
4	Sand	20	28	91	60	0	33			1.80
5	Sand	28	35	111	66	0	35			4.90
6 NOTES:	Stiff Clay without Free Water	35	50	815	63	3,000	0	0.006	0.40	1.80

1. Design depth to subsurface water is about 10 feet.

2. MFAD deformation moduli values based on MFAD 5.1 User Guide, October 2010

LATERAL CAPACITY ANALYSES DESIGN SOIL PARAMETERS FOR <u>UNDRAINED CONDITIONS</u> Airport Distribution Substation

Brownsville, Texas

		Depth to	Soil Layer	LPILE Soil Modulus	Effective Unit	Undrained Shear	Internal Friction	LPILE Soil Strain	Strength	FAD Deformation
Soil	LPILE	Тор	Bottom	k	Weight	Strength	Angle	Factor	Factor	Modulus
Layer	Soil Type	(feet)	(feet)	(pci)	(pcf)	(psf)	(degrees)	e ₅₀	()	(ksi)
1	Stiff Clay without Free Water	0	4	428	115	1,000	0	0.010		0.60
2	Stiff Clay without Free Water	4	8	312	107	400	0	0.017	1.00	0.25
3	Stiff Clay without Free Water	8	18	283	43	250	0	0.023	1.00	0.15
4	Sand	18	25	71	56	0	31			0.85
5	Sand	25	35	91	60	0	33			1.00
6 NOTES :	Stiff Clay without Free Water	35	50	525	56	1,500	0	0.008	0.58	0.90

1. Design depth to subsurface water is about 8 feet.

2. MFAD deformation moduli values based on MFAD 5.1 User Guide, October 2010

SUPPORTING INFORMATION

Contents:

General Notes Unified Soil Classification System

GENERAL NOTES

DESCRIPTION OF SYMBOLS AND ABBREVIATIONS



SAMPLING	WATER LEVEL		FIELD TESTS		
	Water Initially Encountered	N	Standard Penetration Test Resistance (Blows/Ft.)		
Shelby Split Spoon	Water Level After a Specified Period of Time		Hand Penetrometer		
	■ Water Level After a Specified Period of Time	(T)	Torvane		
	Water levels indicated on the soil boring logs are the levels measured in the borehole at the times	(DCP)	Dynamic Cone Penetrometer		
	indicated. Groundwater level variations will occur over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level observations.		Unconfined Compressive Strength		
			Photo-Ionization Detector		
		(OVA)	Organic Vapor Analyzer		

DESCRIPTIVE SOIL CLASSIFICATION

Soil classification is based on the Unified Soil Classification System. Coarse Grained Soils have more than 50% of their dry weight retained on a #200 sieve; their principal descriptors are: boulders, cobbles, gravel or sand. Fine Grained Soils have less than 50% of their dry weight retained on a #200 sieve; they are principally described as clays if they are plastic, and silts if they are slightly plastic or non-plastic. Major constituents may be added as modifiers and minor constituents may be added according to the relative proportions based on grain size. In addition to gradation, coarse-grained soils are defined on the basis of their in-place relative density and fine-grained soils on the basis of their consistency.

LOCATION AND ELEVATION NOTES

Unless otherwise noted, Latitude and Longitude are approximately determined using a hand-held GPS device. The accuracy of such devices is variable. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

STRENGTH TERMS							
RELATIVE DENSITY	OF COARSE-GRAINED SOILS	CONSISTENCY OF FINE-GRAINED SOILS					
	retained on No. 200 sieve.) / Standard Penetration Resistance	(50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance					
Descriptive Term (Density)			Unconfined Compressive Strength Qu, (tsf)	Standard Penetration or N-Value Blows/Ft.			
Very Loose	0 - 3	Very Soft	less than 0.25	0 - 1			
Loose	4 - 9	Soft	0.25 to 0.50	2 - 4			
Medium Dense	10 - 29	Medium Stiff	0.50 to 1.00	4 - 8			
Dense	30 - 50	Stiff	1.00 to 2.00	8 - 15			
Very Dense	> 50	Very Stiff	2.00 to 4.00	15 - 30			
		Hard	> 4.00	> 30			

RELATIVE PROPORTION	S OF SAND AND GRAVEL	RELATIVE PROPORTIONS OF FINES			
Descriptive Term(s) of other constituents Percent of Dry Weight		Descriptive Term(s) of other constituents	Percent of Dry Weight		
Trace	<15	Trace	<5		
With	15-29	With	5-12		
Modifier	Modifier >30		>12		
GRAIN SIZE T	ERMINOLOGY	PLASTICITY DESCRIPTION			
Major Component of Sample Particle Size		Term	Plasticity Index		
Boulders	Over 12 in. (300 mm)	Non-plastic	0		
Cobbles 12 in. to 3 in. (300mm to 75mm)		Low	1 - 10		
Gravel 3 in. to #4 sieve (75mm to 4.75 mm)		Medium	11 - 30		
Sand	Sand #4 to #200 sieve (4.75mm to 0.075mm		> 30		
Silt or Clay Passing #200 sieve (0.075mm)					

UNIFIED SOIL CLASSIFICATION SYSTEM

Terracon GeoReport

					Soil Classification		
ing Group Symbols	and Group Names	Using Laboratory	Fests A	Group Symbol	Group Name ^B		
	Clean Gravels:	$Cu \ge 4$ and $1 \le Cc \le 3^{E}$		GW	Well-graded gravel F		
Gravels: More than 50% of coarse fraction retained on No. 4 sieve s:	Less than 5% fines ^C	Cu < 4 and/or [Cc<1 or Cc>3.0] ^E		GP	Poorly graded gravel F		
	Gravels with Fines:	Fines classify as ML or MH		GM	Silty gravel F, G, H		
	More than 12% fines ^C	Fines classify as CL or C	н	GC	Clayey gravel ^{F, G, H}		
	Clean Sands:	$Cu \ge 6$ and $1 \le Cc \le 3^{E}$		SW	Well-graded sand		
Sands: 50% or more of coarse fraction passes No. 4 sieve	Less than 5% fines D	Cu < 6 and/or [Cc<1 or 0	Cc>3.0] <mark>=</mark>	SP	Poorly graded sand		
	Sands with Fines:	Fines classify as ML or M	ЛΗ	SM	Silty sand G, H, I		
	More than 12% fines ^D	Fines classify as CL or C	н	SC	Clayey sand ^{G, H, I}		
Silts and Clays: Liquid limit less than 50	Inorganic:	PI > 7 and plots on or above "A"		CL	Lean clay ^{K, L, M}		
		PI < 4 or plots below "A" line J		ML	Silt K, L, M		
	Organic:	Liquid limit - oven dried	< 0.75 OL		Organic clay K, L, M, N		
		Liquid limit - not dried		Organic silt K, L, M, O			
Silts and Clays: Liquid limit 50 or more	Inorganic:	PI plots on or above "A"	line	СН	Fat clay ^{K, L, M}		
		PI plots below "A" line	MH		Elastic Silt K, L, M		
	Organia	Liquid limit - oven dried	< 0.75		Organic clay K, L, M, P		
	Organic.	Liquid limit - not dried		ОП	Organic silt ^{K, L, M, Q}		
Primarily	organic matter, dark in co	olor, and organic odor		PT	Peat		
	Gravels: More than 50% of coarse fraction retained on No. 4 sieve Sands: 50% or more of coarse fraction passes No. 4 sieve Silts and Clays: Liquid limit less than 50 Silts and Clays: Liquid limit 50 or more	Gravels: More than 50% of coarse fraction retained on No. 4 sieveClean Gravels: Less than 5% fines CSands: 50% or more of coarse fraction passes No. 4 sieveGravels with Fines: More than 12% fines DSands: 50% or more of coarse fraction passes No. 4 sieveClean Sands: Less than 5% fines DSands with Pines: More than 12% fines DSands with Fines: More than 12% fines DSilts and Clays: Liquid limit less than 50Inorganic: Organic:Silts and Clays: Liquid limit 50 or moreInorganic: Organic:	Clean Gravels: Less than 5% fines CCu \geq 4 and 1 \leq Cc \leq 3 EMore than 50% of coarse fraction retained on No. 4 sieveClean Gravels: Less than 5% fines CCu $<$ 4 and/or [Cc<1 or C	Clean Gravels: Less than 5% fines CCu < 4 and/or [Cc<1 or Cc>3.0] EMore than 50% of coarse fraction retained on No. 4 sieveFines classify as ML or MHGravels with Fines: More than 12% fines CFines classify as ML or MHSands: 50% or more of coarse fraction passes No. 4 sieveClean Sands: Less than 5% fines DCu < 6 and 1 \leq Cc \leq 3 ESands: 50% or more of coarse fraction passes No. 4 sievePlands with Fines: More than 12% fines DFines classify as ML or MHSands with Fines: More than 12% fines DFines classify as ML or MHSilts and Clays: Liquid limit less than 50Pl > 7 and plots on or above "A"Silts and Clays: Liquid limit 50 or moreInorganic:Pl > 7 and plots on or above "A"Silts and Clays: Liquid limit 50 or moreInorganic:Pl plots on or above "A"Silts and Clays: Liquid limit 50 or moreLiquid limit - oven dried Pl plots below "A" lineSilts and Clays: Liquid limit 50 or moreLiquid limit - oven dried Pl plots below "A" lineSilts and Clays: Liquid limit 50 or moreLiquid limit - oven dried Pl plots below "A" lineClean Gray: Liquid limit 50 or moreA Clean Sands: Cu < 6 and/or [Cc<1 or Cc>3.0] E Fines classify as ML or MHSilts and Clays: Liquid limit 1 coven dried Liquid limit - oven dried Liquid limit - not dried< 0.75	In Group Symbols and Group Names Using Laboratory Tests AGroup SymbolGravels: More than 50% of coarse fraction retained on No. 4 sieveClean Gravels: Less than 5% fines C $Cu \ge 4$ and $1 \le Cc \le 3$ EGWGravels with Fines: More than 12% fines CGravels with Fines: Fines classify as ML or MHGMSands: 50% or more of coarse fraction passes No. 4 sieveClean Sands: Less than 5% fines DFines classify as ML or MHGMSands: 50% or more of coarse fraction passes No. 4 sieveClean Sands: Less than 5% fines DCu ≥ 6 and $1 \le Cc \le 3$ ESWSands with Fines: More than 12% fines DCu ≥ 6 and $1 \le Cc \le 3$ ESWSands with Fines: More than 12% fines DFines classify as ML or MHSMSilts and Clays: Liquid limit less than 50Inorganic:PI > 7 and plots on or above "A"CLSilts and Clays: Liquid limit 50 or moreInorganic:Liquid limit - oven dried PI plots on or above "A" lineCHSilts and Clays: Liquid limit 50 or moreInorganic:PI plots on or above "A" lineCHMHCrance: Liquid limit - oven dried Liquid limit - not dried< 0.75		

A Based on the material passing the 3-inch (75-mm) sieve.

^B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

- ^C Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.
- ^D Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

$$E Cu = D_{60}/D_{10}$$
 $Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$

F If soil contains \geq 15% sand, add "with sand" to group name.

^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

- ^H If fines are organic, add "with organic fines" to group name.
- If soil contains \geq 15% gravel, add "with gravel" to group name.
- ^J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.
- K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.
- L If soil contains ≥ 30% plus No. 200 predominantly sand, add "sandy" to group name.
- MIf soil contains \geq 30% plus No. 200, predominantly gravel, add "gravelly" to group name.
- ^N PI \geq 4 and plots on or above "A" line.
- PI < 4 or plots below "A" line.
- P PI plots on or above "A" line.
- QPI plots below "A" line.

