



Date: June 25, 2025
To: All Vendors
Subject: Addendum #2

REFERENCE: B063-25 BPUB Ocelot Substation Construction Bid Package

This Addendum forms part of the contract and clarifies, corrects or modifies original bid document.

NEW SUBMISSION DATE & TIME: JULY 09, 2025 by 5:00 PM

NEW OPENING DATE & TIME: JULY 10, 2025 at 10:00 AM

2nd PRE-BID MANDATORY MEETING: THURSDAY, JUNE 26, 2025 AT 10AM

Vendors can call (956) 214-6020 to attend the pre-bid conference

A 2nd pre-bid mandatory meeting will be held to encourage vendor participation

Question 1: Would BPUB consider granting an extension for the bid submission, moving the due date to Wednesday, July 9th?

Answer 1: BPUB is approving a new submission and opening date and time as listed above.

Question 2: Do you have drawings for the pier foundation and the cap bank foundation?

Answer 2: The drilled pier foundations (excluding the Circuit Switcher) will be designed by the Material Contractor (SEI). The Material Contractor will be providing the anchor bolts for all the pier foundations. For bid purposes, in the "Ocelot Assembly Unit Extended Price" spreadsheet, has estimated pier dimensions and quantities based on past projects. For bid purposes, the rebar will include (8) #8 vertical bars (14'-6" long) and (19) #4 tie hoops, per pier.

We have not received the Circuit Switcher drawings from the manufacturer, so we have not developed a foundation. The manufacturer will be providing the anchor bolts. For bid purposes, in the "Ocelot Assembly Unit Extended Price" spreadsheet, has estimated dimensions and quantities for pier foundations. For bid purposes, the rebar will include (16) #6 vertical bars (14'-6" long) and (17) #4 tie hoops, per pier.

We have not received the capacitor Bank drawings from the manufacturer, so we have not developed a foundation. For bid purposes, in the "Ocelot Assembly Unit Extended Price" spreadsheet, has estimated dimensions and quantities for mat foundations. For bid purposes, the rebar will include (12) #6 horizontal bars (5'-6" long), (16) #6 horizontal bars (7'-6" long), and (12) #5 C-Bars around the perimeter, per mat.

Question 3: Does BPUB have drawing details for the transformers and switchgears?

Answer 3: Attached separately is the latest drawing for the transformer. For the switchgears, please refer to answer 2.

Question 4: May you provide the Material Approval Form found on page 140.

Answer 4: Please disregard the material approval form as that is not a required form for this bid B063-25.

The signature of the company agent, for the acknowledgement of this addendum, shall be required. **Complete information below and return via e-mail to: nespinoza@brownsville-pub.com and hlopez@brownsville-pub.com.**

I hereby acknowledge receipt of this addendum.

Company: _____

Agent Name: _____

Agent Signature: _____

Address: _____

City: _____ **State:** _____ **Zip:** _____

Phone Number: _____ **E-mail address:** _____

If you have any further questions about the Bid, call 956-983-6353.

BY: *Diane Solitaire*
Purchasing